

DEMON® Installations are bringing Nutrient Removal in the US to a new level

Presented By

Andrea Nifong

# Agenda

#### **Section I: INTRODUCTION**

**Section II: DEMON TECHNOLOGY** 

**Section III: DOCUMENTED RESULTS** 



#### Award Winning World-Class Manufacturing

#### Quality \* Safety Cost Schedule \* Innovation

Headquarters: Oklahoma City, OK USA

- Global Leader in MBBR/DAF Technology
- **BNR Specialists**
- Advanced R&D Capabilities
- **Experienced Process Engineering**
- World-wide Delivery Team

WWW is one of the Fastest Growing US Companies

Inc.5000

2013 2012

Inc.500







Top 100 Manufacturing Companies



Top 100 Oklahoma Companies



**Inc.**HirePower

Oklahoma Companies





# Agenda

**Section I: INTRODUCTION** 


**Section II: DEMON TECHNOLOGY** 

**Section III: DOCUMENTED RESULTS** 




#### Drivers for Sidestream DEMON®

- ~1% of Total Plant Influent Flow
- ~20-40% of the Total Plant TN load
- NH<sub>4</sub> Concentration between 900 1,500 mg/L
- Alkalinity/NH4 ratio ≅ 3.5-4.0
- Temperature 30 38°C
- Alkalinity insufficient for complete nitrification
- Insufficient carbon for denitrification




# Innovation in Plant Design to Achieve Energy Neutrality






Lauren Filmore.2012. Roadmap to Energy Neutral Wastewater Treatment. VWEA Annual Education Seminar. Richmond, VA

#### Conventional Nitrification-Denitrification



#### Partial Nitritation + Anammox = Deammonification



### **DEMON®** Process Components



Seed Sludge



Aeration System



Instruments & Controls



Tank



**Blowers** 



Decanter



Mixer



Cyclone



#### **DEMON® Control Strategy - Anammox Enrichment**

- Continual enrichment of anammox
  - Large excess of activity
  - Provides stability
- Ability to Washout NOB if proliferation occurs








Anammox returned to Process

#### DEMON® - Control Strategy

- SBR configuration 6-8 hr/cycles/day
- Last hour of cycle settle and decant
- Active cycle Multiple mini-cycles (10-30 mins):
  - Aerate
  - Mix/fill
  - Mix
- Aeration:
  - DO ~0.2-0.5 mg/L (PID control or constant airflow)
  - pH based aeration control



#### **DEMON®** Status in North America

- DEMON HRSD York River; Started October 2012; operating
- DEMON Industrial Project; started January 2014; operating
- DEMON Alexandria, VA; startup May 2015; operating
- DEMON Philadelphia, PA; 100% design
- DEMON- Guelph, Ontario; starting June 2015; in construction
- DEMON Pierce County, WA; starting 2016; in construction
- DEMON DCWater Blue Plains; starting 2016; in construction
- DEMON Greeley, CO, starting July 2015; in construction
- DEMON Mainstream Alexandria, VA, starting June 2015; in construction



# Agenda

**Section I: INTRODUCTION** 


**Section II: TECHNOLOGY** 

**Section III: DOCUMENTED RESULTS** 







#### Demon® York River WWTP



### NH<sub>4</sub> and TIN Removal Percentages




#### Micronutrient Deficiency - DEMON®




#### Lessons Learned

- Insulate or provide heating during startup
- Provide micronutrients or bi-annual micronutrient screening
- Eliminate sources of dilution water
- Sufficient EQ size and settling
- Temperature control if necessary





### Resource Savings – Methanol Reduction



Mean Methanol addition prior to stable DEMON performance was  $20.33 \pm 0.69$  while the mean methanol addition after stable performance was  $14.82 \pm 0.81$ . t-Test provided p values less than .001.


### Biogas Installations

- Organics management and renewable energy facility
- Converts organic waste into renewable biogas and natural fertilizers
- Full Capacity:
  - 130,000 ton/yr of organic material
  - 3.2 MW of energy
  - 5.4 MW of combined heat and power
  - BioFuel Sources:
    - Food
    - Biosolids
    - FOG





# Ammonia Removal Efficiency





# AlexRenew Upgrades toward Energy Efficiency

 State-of-the-Art Nitrogen Upgrade Program (SANUP)









#### AlexRenew - Sidestream DEMON®

- Seeded May 2015
- During startup Achieving 85% Ammonia Removal
- Current Treatment
   Volume: 85,000 gal/day
- Design Treatment
   Volume: 276,000 gal/day
   @ 1,100 mg/L NH4-N





# AIZ (ACHENTAL-INNTAL-ZILLERTAL) Innsbruck, Austria – Strass WWTP

- Net energy positive plant
- Mainstream treatment by an A/B process
- Sidestream by DEMON deammonification process
- Co-digestion Facility since 2001
- 10 MGD Winter, 5 MGD Summer

Equipment selection based

on power consumption


- BioFuel Sources:
  - Trap Grease
  - Glycerol from Biodeisel
  - Industrial BiologicalProcessing Waste
    - Food Waste









#### **STRASS WWTP DEMONSTRATION** (Full-Scale)



# A LOOK TOWARD THE FUTURE Energy self-sufficient WWTP




Conventional N-removal	DEMON® in side stream DEMON®
Aeration	Aeration
+39,3 Wh /pe d	+37,2 Wh /pe d
Total	Total
+56,5 Wh /pe d	+54,1 Wh /pe d
Gas el.	Gas el.
-42,0 Wh /pe d	-42,0 Wh /pe d
Balance +14,5 Wh/pe d	Balance +12,2 Wh/pe d 15 % reduction




#### A LOOK TOWARD THE FUTURE

Energy self-sufficient WWTP



**DEMON®** in side-A & B Step and main stream **DEMON® &** Demon®+ **DEMON®+ EssDe**® **Aeration Aeration** +31,5 Wh/pe d +16,4 Wh /pe d Total Total +48,4 Wh /pe d +33,3 Wh /pe d Gas el. Gas el. -42,0 Wh /pe d -64,7 Wh /pe d

Balance Balance +6,4 Wh /pe d -31,4Wh /pe d 56 % reduction








### DC Water Upgrades



- A-Stage Maximize carbon capture
- 2. Biosolids Maximize energy recovery
- 3. B-Stage Minimize carbon & energy demand for N & P removal





# Thank you

worldwaterworks.com

1-405-ANAMMOX (262-6669)

Andrea.nifong@worldwaterworks.com